

This Page Is Inserted by IFW Operations
and is not a part of the Official Record

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images may include (but are not limited to):

- BLACK BORDERS
- TEXT CUT OFF AT TOP, BOTTOM OR SIDES
- FADED TEXT
- ILLEGIBLE TEXT
- SKEWED/SLANTED IMAGES
- COLORED PHOTOS
- BLACK OR VERY BLACK AND WHITE DARK PHOTOS
- GRAY SCALE DOCUMENTS

IMAGES ARE BEST AVAILABLE COPY.

**As rescanning documents *will not* correct images,
please do not report the images to the
Image Problem Mailbox.**

(19)



Europäisches Patentamt
European Patent Office
Office européen des brevets



(11) Publication number:

0 463 653 A1

(12)

EUROPEAN PATENT APPLICATION

(21) Application number: 91201211.9

(51) Int. Cl.⁵: **A61K 47/48, A61K 9/06**

(22) Date of filing: 16.05.91

(30) Priority: 07.06.90 GB 9012663

(43) Date of publication of application:
02.01.92 Bulletin 92/01

(84) Designated Contracting States:
DE GB IT

(71) Applicant: **FARMITALIA CARLO ERBA S.r.L.**
Via Carlo Imbonati 24
I-20159 Milano(IT)

(72) Inventor: **De Ponti, Roberto**
Via degli Astri N.22
I-20147 Milan(IT)
Inventor: **Torricelli, Carla**
Via Marco Antonio Colonna n.38
I-20149 Milan(IT)
Inventor: **Lardini, Ercole**
Via Rossini n.14A
I-20090 Pieve Emanuele (Milan)(IT)
Inventor: **Martini, Alessandro**
Via Tranquillo Cremona n.29
I-20145 Milan(IT)
Inventor: **Mongelli, Nicola**
Via Tertulliano n.38
I-20137 Milan(IT)

(54) **Galenic formulations containing cyclodextrins.**

(57) Pharmaceutical compositions comprising a drug, an enhancer of absorption at a mucosal surface and a cyclodextrin, process for their preparation and use of a cyclodextrin in the manufacture of a medicament for administration by absorption at a mucosal surface. Cyclodextrins reduce the toxic effects caused by mucosal absorption enhancers. In particular the compositions are useful in relation to delivery of drugs by the intra-nasal route.

EP 0 463 653 A1

The present invention relates to new pharmaceutical compositions comprising cyclodextrins which are suitable for use in the delivery of drugs by absorption through mucosa. It also relates to a process for the preparation of such compositions and to the use of cyclodextrins in the manufacture of such preparations.

The administration of drugs by absorption through mucosae such as the nasal mucosa has been the subject of considerable interest in recent years. It has been proposed as an alternative to oral administration in cases where drugs are only absorbed poorly by an oral route or are extensively metabolised in the gastrointestinal tract or subjected to first-pass metabolism in the liver. Mucosal absorption is particularly attractive for products such as new physiologically acceptable proteins and polypeptides produced by the methods of biotechnology.

In particular the nasal mucosa has the desirable properties of low enzymatic activity and the avoidance of first-pass metabolism in the liver as the venous system from the nose passes directly into the circulatory system. The nasal mucosa also exhibits moderate permeability to water soluble compounds which is comparable to that of the ileum and gall bladder. This permeability is higher than that for other mucosae such as the vaginal mucosa: while the vaginal epithelium is composed of stratified squamous cells the nasal epithelium is comprised of columnar cells leading to the higher permeability. A high mucosal permeability is clearly desirable for the efficient absorption of drugs across the mucosa.

The efficient delivery of drugs by an intra-nasal route is influenced by the nasal clearance rate as well as the mucosa's permeability. This clearance rate is produced by the coordinated movement of cilia and is known to be highly dependent upon the prevailing physiological and pathological conditions. For instance it is known that both the common cold and polypectomy dramatically increase the nasal clearance rate which leads to a much decreased efficiency of uptake of drug by absorption through the nasal mucosa.

Accordingly, it has been found that for many drugs administration by an intra-nasal route is inefficient due to low uptake of the drug and hence low bio-availability. Much effort has been applied to the development of methods for increasing the efficiency of absorption of drugs across mucosae such as the nasal mucosa. The most popular approach has been to increase the permeability of the mucosa and a large range of potential absorption enhancers which increase the permeability of mucosae have been developed. These are also sometimes called absorption or permeation promoters or enhancers.

Many types of compound have been proposed as absorption enhancers and these include chelating agents, fatty acids, bile acid salts, surfactants other than bile acid salts, fusidic acid and its derivatives, lysophosphatides and cyclic peptide antibiotics. However, many of these enhancers exhibit undesirable toxic side effects.

For example, chelating agents are known to interfere with the ability of calcium ions to control the paracellular transport of peptides and proteins [Lee, "delivery systems for peptide drugs", Plenum, New York (1986)] and are believed to play a vital role in the regulation of ciliary activity [Batts, J.Pharm. Pharmacol., 41, 156-159, (1989)]. Thus the chelating agent sodium edetate which is used in nasal preparations has been found to lead to irreversible damage of the ciliated epithelium at a concentration of 0.1% [Batts, 1989], and must be used at a concentration lower than this, typically 0.05% [Hermans et al Pharmaceutical Research, 4-(6), 445-449 (1987)].

Bile acid salts which can be used as absorption enhancers may be divided into two sub-classes, conjugated and unconjugated bile salts. These include dihydroxy and trihydroxy bile acid salts such as 3 α ,12 α -dihydroxy-5 β cholanoates and 3 α ,7 α ,12 α -trihydroxy-5 β cholanoates. The more efficient absorption enhancers were more hydrophobic, for instance, sodium deoxycholate [Gordon et al, Proc. Natl. Acad. Sci. USA, 82, 7419-7423 (1985)]. It has been found that use of this compound as an absorption enhancer leads to an increase in the permeability of the nasal mucosa which is bidirectional and it is not reversed by washing. Histological evidence suggests that the increased permeability is due to damage caused by extensive loss of the epithelial surface layer. This makes bile acid salts unsuitable for use as absorption enhancers in patients [Hersey & Jackson, J.Pharm. M. Sci., 76, (12), 876-879, (1987)].

Other surfactants which have been used as nasal enhancers include saponin (a glycoside), surfactin (a peptide lipid), and Laureth-9 (a non-ionic detergent, polyoxyethylene-9 lauryl ether) [Hirai, Int. J.Pharm., 9, 165-172, (1981) and Duchateau et al, Int. J.Pharm., 39, 87-89, (1987)]. Laureth-9 shows one of the highest erythrocyte haemolysis effects as well as one of the higher effects of protein release from the nasal mucosa amongst known absorption enhancers [Hirai, Int. J.Pharm., 9, 173-184 (1981) and Longenecker et al, J.Pharm. Sci., 76, 351-355, (1987)]. A 1% solution of Laureth-9 has a "destructing action on the mucosal lining which included multi-focal necrosis, inflammation and exudation, and in some regions, complete removal of epithelial monolayer" [Daugherty et al, Int. J.Pharm., 45, 197-206, (1988)].

Thus the most important disadvantage with the

us of nasal many nasal enhancers is the possibility of side effects which after chronic administration cause irreversible damage to the nasal mucosa. While the absorption enhancer Na tauro 24,25-dihydrofusidate (STDHF) has been found to have good toxicological properties [Lee et al, BioPharm, April, 30-37, (1987)], there remains a need to reduce the toxicity of other absorption enhancers.

It has now been found that when an absorption enhancer is used in combination with a cyclodextrin the undesirable side effects due to the enhancer may be reduced. In particular it has been found that when a cyclodextrin is present the disruptive effects of absorption enhancers on lipid membranes may be reduced.

The present invention therefore provides pharmaceutical compositions suitable for administering a drug to a mucosal surface of a patient, which compositions comprise a drug, an absorption enhancer and a cyclodextrin. In particular the present invention provides compositions comprising a nasal absorption enhancer which are suitable for use as medicaments for therapy by an intra-nasal route.

The invention therefore also provides compositions for use in nasal administration of a drug to a mucosal surface and in particular the nasal mucosa. It also provides compositions comprising an enhancer of absorption at a mucosal surface and a cyclodextrin which are suitable for use in the manufacture of a medicament for use in a method of therapy by absorption of a drug at a mucosal surface and in particular at the nasal mucosa. It also provides for the use of a cyclodextrin in the manufacture of such medicaments.

As a further aspect of the invention there is provided a process for preparing a composition of the invention which comprises mixing a drug, an enhancer of absorption at a mucosal surface and a cyclodextrin.

Cyclodextrins are well known compounds formed by the breakdown of starch. For example, β -cyclodextrin is a cyclic oligosaccharide composed of 7 D-glucose units. Its structure involves a cylindrical cavity capable of including various guest molecules to form host-guest inclusion compounds in the solid state and in solution. Cyclodextrin inclusion compounds have been widely studied and developed for several fully soluble drugs.

The potential toxicity of cyclodextrins in relation to intra-nasal administration has been investigated. The effects of 2-hydroxypropyl β -cyclodextrin on human nasal ciliary epithelial function have been investigated [Messens, 1989 and Hermens et al, 47th Int. Congress of Pharm. Sciences of FIP Amsterdam 31.08-04.09 (1987)]. These studies concluded that this cyclodextrin exerts only a small effect on nasal ciliary movement. Chronic nasal administration in human volunteers has confirmed

this excellent tolerance. No sign of irritation was observed after chronic application of the cyclodextrin on the eye in human volunteers or patients.

The cyclodextrin used in the present invention may be an α , β or γ cyclodextrin, for example depending on which cyclodextrin the enhancer in question binds to most efficiently. It is preferably a β -cyclodextrin because of the low cost of this compound and preferably it is a dehydrated cyclodextrin. β -dehydrated cyclodextrin is therefore especially preferred.

The term "dehydrated cyclodextrin", as used in the present invention, means a cyclodextrin, particularly β -cyclodextrin, which has a water content lower than 5%, preferably lower than 2%, by weight. Clearly, the above definition includes also a cyclodextrin which has the 0% of water content, that is an anhydrous cyclodextrin, for instance anhydrous β -cyclodextrin. Anhydrous β -cyclodextrin is a white crystalline powder, structurally different from hydrated β -cyclodextrin.

To obtain a dehydrated cyclodextrin e.g. dehydrated β -cyclodextrin, the commercially available cyclodextrin, that is a hydrated form containing, e.g. 12% to 14% by weight of water, is typically heated in an oven at a temperature which, depending on the heating time, may vary from about 100°C to about 220°C, preferably from about 100°C to about 140°C. Particularly preferred conditions involve the use of mechanical vacuum and a temperature ranging from about 115°C to about 130°C for 8 hours.

Alternatively, derivatives of α , β and γ cyclodextrins may be used where it is desirable to modify the characteristics of the parent cyclodextrins. In particular more soluble derivatives such as hydroxypropyl, di-methyl and tri-methyl substituted cyclodextrins, cyclodextrins linked with sugar molecules, sulfonated cyclodextrins, carboxylated cyclodextrins, and amino derivatives of cyclodextrins such as diethylaminoethyl cyclodextrins are preferred. A particularly preferred derivative is 2-hydroxypropyl-cyclodextrin. An alternative preferred derivative is a swellable polymer of a cyclodextrin. These differ in their swelling properties from the parent compounds. It is also preferred to use cyclodextrin derivatives which differ with respect of their toxicity from the parent compounds. For example, derivatives which caused reduced haemolysis or kidney damage would be preferred.

The enhancers to be used in combination with a cyclodextrin include chelating agents such as EDTA, EGTA, citric acid, salicylates, alginates, N-acyl derivatives of collagen and amines (N-amino acyl derivatives of β -diketones), fatty acids such as C8 and C10 chain length mono- and di-glycerid extracts of coconut oil (Capmul 8210 and Capmul

MCM 90), monool in or unsaturat d fatty acids, bile acid salts such as 3 α , 12 α -dihydroxy-5 β -cholanoates, Na deoxycholat, Na glycodeoxycholate, Na taurodeoxycholat, 3 α , 7 α , 12 α -trihydroxy-5 β -cholanoates, Na cholate, Na glycocholate, Na taurocholate, other surfactants such as saponin (a glycoside), surfactin (a peptid lipid), a nonionic detergent such as Laureth-9 (polyoxyethylene-9-lauryl ether) and zwitterionic d tergents such as (3-[3-cholamidopropyl-dimethylammonio 1-propane sulfonate), fusidic acid and its derivatives such as Na tauro 24,25-dihydrofusidate (STDHF) and Na glyco 24,25-dihydrofusidate (SGDHF) lysophosphatides such as lysophosphatidylcholine and in particular L- α -lysophosphatidylcholine, cyclic peptide antibiotics such as bacitracin and bacitracin A, preservatives such as methyl p-hydroxybenzoate, propyl p-hydroxybenzoate, chlorobutol, chlorocresol, benzalkonium chloride, chlorexidine and organo-mercuric compounds. Others suitable enhancers which may be used in combination with cyclodextrins include ascorbic acid, basic amino acids and/or their salts, glycyrrhetic acid and glycyrrhizin, O-acylcarnitine derivatives like octanoyl carnitine, lauroyl carnitine, phosphatidyl carnitine and derivatives, palmitoyl carnitine, and malonates, e.g. diethyleneoxym thylene malonate.

Any active drug substance may be used in the composition of the present invention.

Examples of drugs are:

Proteins and peptides such as insulin (hexameric/dimeric/monomeric forms), gentamicin, glucagon, growth hormone (Somatotrophin), calcitonins and synthetic modifications thereof, enkephalins, interferons (especially Alpha-2 interferon for treatment of common colds), luteinising hormone-releasing hormone (LHRH) and analogues (Nafarelin, Buserelin, Leuporelin, Goserelin), GHRH (growth hormone releasing hormone), secretin, nifedipine, bradykin antagonists, GRF (growth releasing factor), THF, TRH (thyrotropin releasing hormone), ACTH analogues, IGF (insulin-like growth factors) CGRP (calcitonin gene related peptide), atrial natriuretic peptide, vasopressin and analogues (DDAVP, lypressin), metoclopramide, migraine treatment(dihydroergotamine, ergometrine, ergotamine, pizotizin), nasal vaccines (particularly AIDS vaccines), FACTOR VIII;

Antibiotics and antimicrobial agents such as tetracycline hydrochloride, leucomycin, penicillin, penicillin derivatives and erythromycin, chemotherapeutic agents such as sulphathiazole and nitrofurazon; local anaesthetics such as benzocaine; vasoconstrictors such as phenylephrine hydrochloride, tetrahydrozoline hydrochlorid, naphazolin nitrat, oxymetazolin hydrochlorid and tramazoline hydrochlorid; cardiotonics such

as digitalis and digoxin; vasodilators such as nitroglycerin and papaverin hydrochlorid; antiseptics such as chlorhexidin hydrochlorid, hexylresorcinol, dequalinium chloride and ethacridin; enzymes such as lysozyme chloride, dextranase; bone metabolism controlling agents such as vitamin D₃ and active vitamin D₃; sex hormones; hypotensives; sedatives; anxiolytics and anti-tumor agents;

Steroidal anti-inflammatory agents such as hydrocortisone, prednisone, fluticasone, predonisolone, triamcinolone, triamcinolone acetate, dexamethasone, betamethasone, beclomethasone, and beclomethasone dipropionate; non-steroidal anti-inflammatory agents such as acetaminophen, aspirin, aminopyrine, phenylbutazone, mefenamic acid, ibuprofen, ibufenac, alclofenac, diclofenac sodium, indomethacin, colchicine, probenecid, phenactin, sulpyrine, sulfenamid acid; enzymatic anti-inflammatory agents such as chymotrypsin and bromelain seratiopeptidase; antihistaminic agents such as diphenhydramine hydrochloride, chlorpheniramine maleate and clemastine; anti-allergic agents (antitussive-expectorant antasthmatic agents such as sodium cromoglycate, codeine phosphate, and isoproterenol hydrochloride.

Other examples of active substances may be steroids, for instance medroxyprogesterone acetate (MPA), progesterone, testosterone, 6-methyleneandrost-1, 4-diene-3,17-dione and the like; antibiotics such as e.g., griseofulvin, cephalosporin, penems and the like; antidepressant drugs such as, e.g., benzodiazepines, e.g. temazepam, oxazepam, diazepam, nitrazepam and the like; immunomodulators such as, e.g., 2-cyano-3-(1,4-dihydro-1-phenyl-(1)-benzothiofuran) (4,3-C)-pyrazol-3-yl-3-oxo-N-phenylpropanamide and the like; antiinflammatory agents such as, e.g., indoprofen, ketoprofen, flufenamic acid and the like; antineoplastic agents such as, e.g. anthracycline glycosides, e.g. idarubicin (i.e. 4-dimethoxydaunorubicin) and 3'-desamine-3'-(3-cyano-4-morpholinyl)-doxorubicin and the like, etoposide, teniposide and other podophyllotoxins.

The compositions are especially suitable for the administration of physiologically active polypeptides.

All possible isomers, stereoisomers and optical isomers of drugs and their mixtures may be used in the compositions of the present invention. Metabolites and metabolic precursors or bioprecursors of drugs may also be used.

The relative proportions and dosages of the components in the compositions will vary with the nature of the components, the route of administration, the frequency of administration and the age, weight and condition of the patient. The composition

tions will comprise a sufficient amount of cyclodextrin to alleviate the damage to the mucosa caused by absorption enhancer.

The amount of drug, absorption enhancer and cyclodextrin may be decided on a case by case basis. The competition between a drug and an enhancer to form a complex with the cyclodextrin can be a factor to consider. A drug and a cyclodextrin are suitably present in a composition according to the invention in a molar ratio of drug : cyclodextrin of from 1:0.05 to 1:30, for example from 1:0.5 to 1:3. Similarly, an enhancer and a cyclodextrin may be present in a molar ratio of enhancer:cyclodextrin of from 1:0.05 to 1:30, for example from 1:0.5 to 1:3.

The compositions may be suitable for administration by nasal, oral, rectal, buccal, intestinal, tracheal or vaginal routes, and especially nasal administration. They may further comprise additional ingredients as are conventionally found in such compositions, for instance suitable carriers, or diluents, as well as lubricants, binders, colourants, odor improvers, preservatives and surface-active agents.

Compositions of the present invention suitable for nasal administration may be in form of an aqueous solution for administration obtained by dissolving the drug, enhancer and cyclodextrin in the same aqueous medium.

Solid state preparations may also be successfully used for nasal administration. These may range from a simple physical mixture of the drug, enhancer and the cyclodextrin to a complex or inclusion compound between the enhancer and cyclodextrin mixed with the drug. Simple mixtures may be obtained for example by tumble mixing or sieving of the components and in this aspect of the invention the use of dehydrated cyclodextrin and in particular dehydrated β -cyclodextrin is preferred as a solution is formed on administration by water absorption from the mucosa. Inclusion complexes between the enhancer and cyclodextrin may be obtained by precipitation, freeze-drying, solvent evaporation, co-grinding, spray-drying, kneading or vapour solvent exposure. The preparation of such complexes is described for example in "Cyclodextrins and their industrial uses", Ed. Duchene, Editions de Sante, (1987) and Szejtli, "Cyclodextrins and their inclusion complexes", Akademiai Kiado, Budapest, (1982). Inclusion complexes may be mixed with the drug by known methods, such as for example tumble mixing or sieving.

Solid compositions suitable for nasal delivery may for example be in the form of a powdery composition comprising at least about 90% by weight of a low molecular weight cellulose as described in EP-A-28359. The cellulose is preferably

hydroxymethyl cellulose, hydroxypropyl cellulose or hydroxypropylmethyl cellulose and most preferably hydroxypropyl cellulose. Another suitable composition comprises a water-absorbing and water-insoluble base such as microcrystalline cellulose, as described in EP-A-0122036.

Alternatively, solid compositions suitable for nasal administration may comprise microspheres of starch derivatives, gelatin, albumin, collagen, dextran, dextran derivatives such as anionic derivatives for example a carboxylated or sulphated dextran or cationic derivatives for example diethylamino ethyl or a quaternary amino ethyl dextran, or similar materials as described in WO-A-88/09163. The microspheres are typically water-swelling and water insoluble. Preferably they are starch or dextran derived and are cross-linked such as Spherox (Trade Mark). microspheres composed of cross-linked starch. Such microspheres form a gel on administration which adheres to the mucosa and enhances absorption. This occurs through shrinkage of the epithelial cells, [Illum et al, Int.J.Pharm., 46, 261-265 (1988), Illum et al, Int.J.Pharm. 39, 189-199 (1987), Bjork et al, Int.J.Pharm., 47, 233-238 (1988) and Illum et al, 15th Int. Symposium on controlled delivery of bioactive material, August 15-19 (1988), Basel]. The microspheres are loaded with a drug, typically by freeze-drying a dispersion of the microspheres in a solution of the drug. The microspheres may be loaded with or mixed with the absorption enhancers and/or cyclodextrin.

At least 90 wt % of particles of a composition for nasal delivery should have a particle diameter of from 10 to 250 μm such as from 10 to 100 μm and, more preferably, from 10 to 50 μm . Preferably all particles are within one of these size ranges. Solid state compositions may be administered intra-nasally by spraying. Such administration may be by use of a nasal insufflator device.

In vitro and in vivo experiments were carried out to test cyclodextrins' ability to protect the nasal mucosa from the undesirable effects of enhancers. The following experiments illustrate but don't limit the invention.

In vitro experiments

It is well known that all animal cells are contained in a membrane whose constituents are mainly lipids, phospholipids, glycolipids, and proteins. This was simulated in a simple way using the phospholipid dipalmitoylphosphatidylcholine [DPPC] in such a condition to have a bilayer structure of the DPPC (the bilayer structure is encountered in cell membranes) [Yoshioka et al, J.Colloid Interface Science, 133(2), 442-446 (1989)].

It has now been found that the bilayer structure is destroyed by Lauric acid and that the addition

of cyclodextrins has an effect in making this destructuring effect less prominent or negligible.

The addition of cyclodextrins is useful in making the parameters controlled in the in-vitro test reversible towards the initial values for DPPC alone. This experimental work, executed with an enhancer, Laureth-9, that is well known for destructuring membranes, demonstrates that cyclodextrins have a protective effect for the cell membranes making the interaction of the enhancer with the DPPC constituent of the in-vitro bilayer reversible.

A Differential Scanning Calorimetry (DSC) Mettler TA 3000 equipped with a TC10 processor, a DSC 20 cell (placed in a refrigerator) and a Wenger Matrix printer was used.

100 mg of DPPC (m.w. 734, Nippon Fine Chemical lot. PA631215 or Sigma Lot. 116F-8365) were added to 1 mL of buffer solution, pH=7 (100 mL of the buffer solution at pH=7 were prepared adding 50 mL of KH_2PO_4 0.1M and 29 mL of NaOH 0.1M to a flask of 100 mL brought to volume with distilled water). The mixture was vigorously shaken and left for 1 hour at $+50^\circ\text{C}$ for annealing. 150 μL of the mixture obtained were transferred into a 160 μL aluminium pan and sealed immediately. As reference a 160 μL sealed aluminium pan containing 150 μL of buffer solution was used.

DSC runs were performed from $+10^\circ\text{C}$ to $+80^\circ\text{C}$ at a scan rate of 1K/min. The destructuring action of the absorption enhancers Laureth-9 (m.w. 582, Sigma Lot. 77-0458) [L9], L- α -Lysophosphatidylcholine Palmitoyl (m.w.496, Sigma Lot.70H-8383) [LPC], Deoxycholic Acid Sodium Salt (m.w.415, Sigma Lot.108F-0331)[DCH] was tested adding the weighted amount of enhancer to DPPC before adding 1ml of buffer solution. Blanks of all cyclodextrins tested were performed with no interference on the signals referred to DPPC; these were found in agreement with literature data [Yoshioka et al 1989 and Kelker H. and Hatz R., "Handbook of Liquid Crystals", Verlag Chemie, Basel; 1980, page 568, Figure 12.16].

The cyclodextrins used in this study were: 2-hydroxypropyl- β -cyclodextrin (m.w. about 1300, Roquette Lot. 0069 or Janssen Lot. 26322) [2-HP/ β CD],

β -cyclodextrin tetradecasulfate (m.w. 2464, Farmitalia Carlo Erba R&D, Lot. CF/72 [β CDS], α -cyclodextrin (m.w. 972, Wacker Chemie) [α CD], γ -cyclodextrin (m.w. 1297, Wacker Chemie) [γ -CD], Water soluble polymer of cyclodextrin (Chinoil Lot. CYL 97/1) [CYLCD].

Weighted amounts of the used cyclodextrins were added to DPPC or DPPC+L9 mixture before adding the buffer solution (1mL).

The samples analyzed in DSC were pure substances and their binary and ternary mixtures. The composition of the various samples was as follows

Figure 1	Dipalmitoylphosphatidylcholine [DPPC] only;
Figure 2	a) Laureth 9 [L9]
5	b) L- α -Lysophosphatidylcholine Palmitoyl [LPC]
	c) Deoxycholic Acid Sodium Salt [DCH]
Figure 3	a) α -cyclodextrin [α -CD]
10	b) 2-hydroxypropyl- β -cyclodextrin [2-HP/ β CD]
	c) γ -cyclodextrin [γ -CD]
	d) β -cyclodextrin tetradecasulfate [β -CDS]
15	e) water-soluble polymer of cyclodextrin [CYLCD]
Figure 4	a) DPPC
	b) 10/1 mol/mol DPPC/L9
20	c) 10/1/1 mol/mol/mol DPPC/L9/2HP- β CD
Figure 5	a) DPPC
	b) 5/1 mol/mol DPPC/L9
	c) 5/1/1 mol/mol/mol DPPC/L9/2HP- β CD
25	Figure 6
	a) DPPC
	b) 2/1 mol/mol DPPC/L9
	c) 2/1/1 mol/mol/mol DPPC/L9/2HP- β CD
30	Figure 7
	a) DPPC
	b) 1/1 mol/mol DPPC/L9
	c) 1/1/4 mol/mol/mol DPPC/L9/2HP- β CD
35	Figure 8
	a) DPPC
	b) 10/1 mol/mol DPPC/L9
	c) 10/1/1 mol/mol/mol DPPC/L9/ β CDS
40	Figure 9
	a) DPPC
	b) 5/1 mol/mol DPPC/L9
	c) 5/1/1 mol/mol/mol DPPC/L9/ β CDS
45	Figure 10
	a) DPPC
	b) 2/1 mol/mol DPPC/L9
	c) 2/1/1 mol/mol/mol DPPC/L9/ β CDS
50	Figure 11
	a) DPPC
	b) 10/1 mol/mol DPPC/L9
	c) 10/1/1 mol/mol/mol DPPC/L9/ α CD
55	Figure 12
	a) DPPC
	b) 5/1 mol/mol DPPC/L9
	c) 5/1/1 mol/mol/mol DPPC/L9/ α CD
	Figure 13
	a) DPPC
	b) 2/1 mol/mol DPPC/L9
	c) 2/1/1 mol/mol/mol DPPC/L9/ α CD
	Figure 14
	a) DPPC
	b) 10/1 mol/mol DPPC/L9
	c) 10/1/1 mol/mol/mol DPPC/L9/ γ CD

Figur 15	a)DPPC	
	b)5/1 mol/mol DPPC/L9	
	C)5/1/1 mol/mol/mol DPPC/L9/yCD	
Figur 16	a)DPPC	
	b)2/1 mol/mol DPPC/L9	5
	C)2/1/1 mol/mol/mol DPPC/L9/yCD	
Figure 17	a)DPPC	
	b)10/1 mol/mol DPPC/L9	
	C)10/1/1 mol/mol/mol DPPC/L9/CYLCD	10
Figure 18	a)DPPC	
	b)5/1 mol/mol DPPC/L9	
	C)5/1/1 mol/mol/mol DPPC/L9/CYLCD	
Figure 19	a)DPPC	15
	b)2/1 mol/mol DPPC/L9	
	c)2/1/1 mol/mol/mol DPPC/L9/CYLCD	
Figure 20	a)DPPC	
	b)10/1 mol/mol DPPC/LPC	20
	c)10/1/1 mol/mol/mol DPPC/LPC/yCD	
Figure 21	a)DPPC	
	b)5/1 mol/mol DPPC/LPC	
	c)5/1/1 mol/mol/mol DPPC/LPC/yCD	25
Figure 22	a)DPPC	
	b)5/1 mol/mol DPPC/LPC	
	c)5/1/1 mol/mol/mol DPPC/LPC/ α CD	30
Figure 23	a)DPPC	
	b)2/1 mol/mol DPPC/DCH	
	c)2/1/1 mol/mol/mol DPPC/DCH/2HP- β CD	35

The typical appearance of the DSC curve of sample 1 is shown in Fig. 1. It is evident that two thermal events are observed, an endothermal one at a lower temperature (about 37.5 °C) and another endothermal peak at a higher temperature (about 43.5 °C). The latter event can be attributed to the gel-liquid crystal transition. The results (DSC curves) are shown and commented in Fig.1 through Fig.23.

Figure 1 This is typical DSC curve of DPPC. In which two thermal events are observed. An endothermal pretransition peak at a lower temperature about 37.5 °C and another one transition peak at higher temperature about 43.6 °C. The latter transition peak can be attributed to the gel-liquid crystal transition.

Figure 2 The enhancers don't give any interference with the DPPC curve.

Figure 3 The cyclodextrins don't give any interference with DPPC curve. No interference was observed also for

binary samples composed of DPPC adding various kinds of cyclodextrins.

Figure 4 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.

c) Addition of 2-hydroxypropyl- β -cyclodextrin gives a DSC curve of identical pattern as DPPC as is.

Figure 5 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.

c) Addition of 2-hydroxypropyl- β -cyclodextrin turns the DSC curve more like the pattern of DPPC as is.

Figure 6 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering and a broadening of transition peak temperature.

c) Addition of 2-hydroxypropyl- β -cyclodextrin turns the DSC curve more like the pattern of DPPC as is.

Figure 7 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering and a broadening of transition peak temperature.

c) Addition of 2-hydroxypropyl- β -cyclodextrin gives a DSC curve of identical pattern as DPPC as is.

Figure 8 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.

c) Addition of β -cyclodextrin-tetradecasulfate does not give a DSC curve much more similar to DPPC alone.

Figure 9 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.

c) Addition of β -cyclodextrin-tetradecasulfate gives origin to modified and complex domains.

Figure 10 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering and a broadening of transition peak temperature.

c) Addition of β -cyclodextrin-tetradecasulfate gives origin to modified and complex domains.

Figure 11 a) DSC curve of DPPC.
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak

- t mperatur .
- c) Addition of α -cyclodextrin does not give a DSC curve much more similar to DPPC alone .
- Figure12 a) DSC curve of DPPC. 5
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.
c) Addition of α -cyclodextrin turns the DSC curve more like the pattern of DPPC as is. 10
- Figure13 a) DSC curve of DPPC. 15
b) Addition of Laureth 9 to DPPC gives a lowering and a broadening of transition peak temperature.
c) Addition of α -cyclodextrin gives origin to modified and complex domains.
- Figure14 a) DSC curve of DPPC. 20
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.
c) Addition of γ -cyclodextrin turns the DSC curve more like the pattern of DPPC as is. 25
- Figure15 a) DSC curve of DPPC. 30
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.
c) Addition of γ -cyclodextrin turns the DSC curve more like the pattern of DPPC as is.
- Figure16 a) DSC curve of DPPC. 35
b) Addition of Laureth 9 to DPPC gives a lowering and a broadening of transition peak temperature.
c) Addition of γ -cyclodextrin turns the DSC curve more like the pattern of DPPC as is.
- Figure17 a) DSC curve of DPPC. 40
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.
c) Addition of CYLCD turns the DSC curve more like the pattern of DPPC as is. 45
- Figure18 a) DSC curve of DPPC. 50
b) Addition of Laureth 9 to DPPC gives a lowering of transition peak temperature.
c) Addition of CYLCD turns the DSC curve more like the pattern of DPPC as is.
- Figur 19 a) DSC curve of DPPC. 55
b) Addition of Laureth 9 to DPPC gives a lowering and a broadening of transition peak temperature .
c) Addition of CYLCD turns the

DSC curve more like the pattern of DPPC as is.

Figure 20

- a) DSC curve of DPPC.
b) Addition of LPC to DPPC gives a lowering of transition peak temperature.
c) Addition of γ -cyclodextrin gives a DSC curve of identical pattern as DPPC as is.

Figure21

- a) DSC curve of DPPC.
b) Addition of LPC to DPPC gives a lowering of transition peak temperature.
c) Addition of γ -cyclodextrin turns the DSC curve more like the pattern of DPPC as is.

Figure22

- a) DSC curve of DPPC.
b) Addition of LPC to DPPC gives a lowering and broadening of transition peak temperature.
c) Addition of α -cyclodextrin turns the DSC curve more like the pattern of DPPC as is.

Figure23

- a) DSC curve of DPPC.
b) Addition of DCH to DPPC gives a lowering and a broadening of transition peak temperature.
c) Addition of 2-hydroxypropyl- β -cyclodextrin turns the DSC curve more like the pattern of DPPC as is.

In vivo experiments

The rat model has been shown to be useful in identifying the histological effects of nasal formulations. A small dose volume administered to one side of the rat nasal cavity only, does not leak into the undosed side. Treated tissue can then be directly compared to untreated tissue in the same animal when complete cross-sections are made. Groups of four male Wistar rats (Sutton Bonnington, 250g approximately) were used in all experiments. Animals were anaesthetised intraperitoneally with "Sagatal" (sodium pentobarbitone 60 mg/ml; 72 mg/kg) and a tracheotomy performed. 25 μ l of the nasal formulation was administered to the right nostril of each animal.

The following nasal formulations were administered :

- (i) Phosphate Buffer (pH 7.3) .
- (ii) Laureth-9 Solution 0.9% w/v in phosphate buffer (9 mg/ml; 0.9 mg/kg in 25 μ l).
- (iii) 2-Hydroxypropyl- β -Cyclodextrin(2HP- β CD) 81.22 mg/ml in phosphate buffer. The concentration of HP β C selected was chosen according to the molar ratio of 1:4 (Laureth-9 : 2HP- β CD determined as being the least damaging to red

blood cells.

(iv) Laureth-9 0.9% w/v (9 mg/ml) co-administered with 2HP- β CD 81.22 mg/ml in phosphate buffer (mol. ratio 1:4).

Perfusions were successful in all cases judging by the distribution of yellow fixative.

60 Minutes after administration of the intranasal dose tissue was fixed by cardiac perfusion of a prewash solution (for 2 minutes) followed by Bouin Hollande aqueous fixative (for 15 minutes). Animals were then decapitated, soft tissue removed and skulls placed in fixative baths overnight.

Specimens were decalcified in 20% EDTA solution for a minimum of 3 weeks after which time region ii of the cavity, between the incisor teeth and incisive papilla, was isolated for further processing. Decalcification was followed by dehydration and wax embedding. Each specimen was orientated so that complete transverse cross-sections of the nasal cavity were produced with the anterior face presented for cutting first. Sections were cut serially at 7 μ m thickness, mounted and stained with haematoxylin and eosin. Acidic mucopolysaccharides were demonstrated with alcian blue stain (in 3% acetic acid).

Cross-sections were examined with the light microscope. The photomicrographs so obtained are shown in Fig. 24 through 27. In each section, tissue on the dosed side of the nasal cavity was compared with that on the undosed control side. In the region investigated, the nasal cavity is lined by a ciliated pseudostratified columnar epithelium on the septum, which is rich in goblet cells (ie respiratory epithelium) while turbinate epithelium is generally thinner, sparsely ciliated and contains few goblet cells.

In all photomicrographs the dosed right side appears on the left and the following key applies:

S = Nasal Septum

Nt = Nasoturbinate

C = Cartilage

G = Goblet Cell

m = mucus

v = vascular sinus

L / R = Left / Right side of the nasal cavity (actual)

→ = Epithelium-lamina propria junction.

Figure 24a : Photomicrograph of a section through the nasal cavity of a rat dosed with phosphate buffer (pH 7.3) showing ciliated pseudostratified columnar epithelium covering both sides of the nasal septum.

Figure 24b : Photomicrograph of a section through the nasal cavity of a rat dosed with phosphate buffer (pH 7.3) stained with alcian blue to show acidic mucopolysaccharides.

Figure 25a : Photomicrograph of a section through the nasal cavity of a rat dosed with

Laureth-9 0.9% w/v in phosphate buffer (pH 7.3) showing severe disruption of the epithelium on the dosed side.

Figure 25b : Photomicrograph of a section through the nasal cavity of a rat dosed with Laureth-9 0.9% w/v in phosphate buffer (pH 7.3) stained with alcian blue showing epithelium disruption with loss of mucus from goblet cells on the dosed side.

Figure 26a : Photomicrograph of a section through the nasal cavity of a rat dosed with 2HP- β CD 81.22 mg/kg in phosphate buffer (pH 7.3)

Figure 26b : Photomicrograph of a section through the nasal cavity of a rat dosed with 2HP- β CD 81.22 mg/kg in phosphate buffer (pH 7.3) stained with alcian blue showing signs of epithelial interaction on the dosed side.

Figure 27a : Photomicrograph of a section through the nasal cavity of a rat dosed with the combined Laureth-9 (0.9% w/v) and 2HP- β CD (81.22 mg/kg) formulation (in phosphate buffer pH 7.3). Epithelium on the dosed side appears more disordered and cell nuclei are more densely stained and more closely packed towards the basal membrane than on the undosed side.

Figure 27b : Photomicrograph of a section through the nasal cavity of a rat dosed with the combined Laureth-9 (0.9% w/v) and 2HP- β CD (81.22 mg/kg) formulation (in phosphate buffer pH 7.3) stained with alcian blue. Mucus discharged from goblet cells is present in the lumen of the dosed side of the cavity and dosed epithelium is more disordered than that on the undosed side.

The comments to these figures are given herebelow:

Figure 24

Phosphate buffer resulted in few effects on contact with the nasal epithelium.

There was slightly more mucus present on the luminal surface of the epithelium on the dosed side of the nasal cavity but there was no discernible difference in epithelium thickness on the two sides of the septum. The ciliated pseudostratified columnar epithelium appeared the same on both the treated and untreated sides with no obvious signs of interaction with the nasal dose.

Figure 25

The effects of 0.9% w/v Laureth-9 were severe and widespread in the dosed side of the rat nasal cavity. The epithelium was disrupted with significant cell loss and mucus discharged into the lumen of the cavity. This resulted in reduction of the membrane to a thin layer of cells in some places. Effects were observed on the septum, tur-

binates and lateral wall on the dosed side; epithelium on the undosed side was unaffected.

Figure 26

Rat nasal tissue exposed to 2HP- β CD showed some signs of interaction between the epithelium and the nasal dose but to a far lesser extent than 0.9% Laureth-9 after one hour exposure. Respiratory tract infection in this group was a particular problem with infected tissue identified in all of the animals, though to varying degrees.

There was a slight reduction in the thickness of the septal epithelium on the dosed side compared to that covering the undosed septum, but no cell loss was observed and cilia were still present on the luminal cell surfaces. Generally there was slightly more mucus discharged into the dosed side of the cavity, except where infection occurred in the undosed side where mucus production was also increased.

On close inspection, the epithelium on the dosed side appeared to be more "disordered" than the control tissue with the line of cilia basal bodies at the luminal surface interrupted at intervals. The nuclei of the epithelial cells on the dosed side tended to be smaller and more irregularly shaped than the large rounded nuclei in the untreated epithelium, particularly over the central septum areas. Also dosed nuclei were stained more densely obscuring intranuclear detail and tended to be more closely packed at the basal membrane. These observations suggest some interaction between dose and tissue, possibly in the early stages.

Figure 27

The effects of the combined enhancer system were similar to those produced by cyclodextrin alone over 60 minutes, but the disorder of the epithelium and effect on the nuclei was more pronounced, particularly in turbinate epithelium. Again, a complete and relatively thick epithelium was maintained with no surface cell loss, but mucus discharge into the dosed side of the cavity was further increased and epithelium thickness reduced compared with the control tissue.

These observations suggest that the co-administration of 2HP- β CD with Laureth-9 solution in the ratio 4:1 results in a significant decrease in the degree of damage to the nasal epithelium over 60 minutes. Some interaction between the 2HP- β CD and nasal epithelium was indicated by increases in mucus discharge, changes in nuclei appearance and an increase in epithelium "disorder". This latter effect is possibly the result of mucus discharge emptying goblet cells so that their structure be-

comes more fluid and susceptible to disarrangement. Such interactions were more marked in the combined formulation but large scale cell loss such as occurred with Laureth-9 alone in solution, was not observed in any other group of animals.

Claims

1. A pharmaceutical composition suitable for administering a drug to a mucosal surface of a patient, which composition comprises a drug, an absorption enhancer and a cyclodextrin.
2. A composition according to claim 1 in which the absorption enhancer is a nasal absorption enhancer.
3. A composition according to claim 1 or 2 in which the absorption enhancer is present as an inclusion complex of the cyclodextrin.
4. A composition according to any one of the preceding claims in which the cyclodextrin is a soluble cyclodextrin derivative or a swellable polymer of cyclodextrin.
5. A composition according to any one of the preceding claims in which the cyclodextrin is β -cyclodextrin or a β -cyclodextrin derivative.
6. A composition according to claim 5 in which the cyclodextrin is dehydrated β -cyclodextrin or 2-hydroxypropyl β -cyclodextrin.
7. A composition according to any one of the preceding claims which further comprises water swellable microspheres of crosslinked starch or dextran.
8. A composition according to any one of the preceding claims, wherein the drug is a physiologically active polypeptide.
9. A composition according to any one of the preceding claims for use in nasal administration of a drug.
10. A composition comprising an enhancer of absorption at a mucosal surface and a cyclodextrin.
11. Use of a cyclodextrin in the manufacture of a medicament for use in administering a drug and an absorption enhancer to a mucosal surface.
12. Use according to claim 11 in the manufacture of a medicament for use in nasal administration.

tion of the drug.

13. A process for preparing a composition as claimed in any one of claims 1 to 8 which comprises mixing the drug, the absorption enhancer and the cyclodextrin. 5
14. A process according to claim 13 which comprises preparing an inclusion complex of the absorption enhancer and the cyclodextrin, and mixing the inclusion complex with the drug. 10
15. A composition according to claim 10 which is substantially as described in any one of Samples Nos. 1 to 15. 15

20

25

30

35

40

45

50

55




Fig. 1




Fig. 2




Fig. 3




Fig. 4




Fig. 5




Fig. 6




Fig. 7




Fig. 8




Fig. 9




Fig. 10




Fig. 11




Fig. 12




Fig. 13




Fig. 14




Fig. 15




Fig. 16




Fig. 17




Fig. 18




Fig. 19




Fig. 20




Fig. 21




Fig. 22




Fig. 23




Fig. 24a




Fig. 24b




Fig. 25a




Fig. 25b




Fig. 26a




Fig. 26b




Fig. 27a




Fig. 27b



European Patent
Office

PARTIAL EUROPEAN SEARCH REPORT

which under Rule 45 of the European Patent Convention
shall be considered, for the purposes of subsequent
proceedings, as the European search report

Application Number

EP 91 20 1211

DOCUMENTS CONSIDERED TO BE RELEVANT			
Category	Citation of document with indication, where appropriate, of relevant passages	Relevant to claim	CLASSIFICATION OF THE APPLICATION (Int. Cl.5)
X	EP-A-0 302 772 (TOYO JOZO CO.) * Page 2, line 51 - page 3, line 12; page 3, lines 35-50; page 3, line 59; claims *	1-6,8-15	A 61 K 47/48 A 61 K 9/06
X,Y	EP-A-0 308 181 (NOVO INDUSTRI A/S) * Column 3, lines 54-65; column 4, lines 1-22; claims 1,5,6,7,8,12 *	1-15	
D,Y	WO-A-8 809 163 (COSMAS-DAMIAN LTD) * Page 4, lines 5-13; page 9, line 4 - page 10, line 3; page 11, line 2; claims *	1-15	
X	EP-A-0 349 091 (W.A. HERMENS et al.) * Claims 1,2,4 *	1-6,8-15	
X	EP-A-0 300 526 (JANSSEN PHARMACEUTICA) * Page 2, line 46 - page 3, line 52; page 8, lines 14-32 *	1-6,8-15	
			TECHNICAL FIELDS SEARCHED (Int. Cl.5)
			A 61 K
INCOMPLETE SEARCH			
<p>The Search Division considers that the present European patent application does not comply with the provisions of the European Patent Convention to such an extent that it is not possible to carry out a meaningful search into the state of the art on the basis of some of the claims</p> <p>Claims searched completely : Claims searched incompletely : 1-15 Claims not searched : Reason for the limitation of the search:</p> <p>The terms drug "and absorption enhancer are too large" and not corresponding to the demand of clarity of (art. 84 EPC). They have been interpreted in the light of the examples.</p>			
Place of search THE HAGUE		Date of completion of the search 11-10-1991	Examiner BERTE M.J.
CATEGORY OF CITED DOCUMENTS		T : theory or principle underlying the invention E : earlier patent document, but published on, or after the filing date D : document cited in the application L : document cited for other reasons ----- & : member of the same patent family, corresponding document	
X : particularly relevant if taken alone Y : particularly relevant if combined with another document of the same category A : technological background O : non-written disclosure P : intermediate document			